

BRUHAT BANGALORE MAHANAGARA PALIKE


BBMP/2015-16/RD/WORK_INDENT18677/CALL-2

APPROVED SCHEDULE - B


EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016


Construction of Drain, Providing Covering slab and Kerb Stone from MS Palya Circle to Vidyaranyapura Connecting Road (RHS) in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N THIRUNAGENDRA		
				In Figures		In Words
1	486.98	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	81.0	39445.38	Rupees Eighty One Only
2	13.2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5000.0	66000.00	Rupees Five Thousand Only
3	128.16	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4100.0	525456.00	Rupees Four Thousand One Hundred Only
4	39.38	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5400.0	212652.00	Rupees Five Thousand Four Hundred Only
5	238.8	Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	999.0	238561.20	Rupees Nine Hundred Ninety Nine Only
6	97.74	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments,, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc complete as per specifications and directions of engineer in charge of the work	Cum	6120.0	598168.80	Rupees Six Thousand One Hundred Twenty Only


 Executive Engineer
 Byatarayanapura Division
 Yelahanka Zone, B.B.M.P.
 Bangalore - 560 092

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N THIRUNAGENDRA		
				In Figures		In Words
7	6.84	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	72000.0	492480.00	Rupees Seventy Two Thousand Only
8	601.2	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	300.0	180360.00	Rupees Three Hundred Only
9	1733	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc complete as per specifications and directions of engineer in charge of the work	Nos	320.0	554560.00	Rupees Three Hundred Twenty Only
10	269.5	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	25.0	6737.50	Rupees Twenty Five Only
11	269.5	Providing and applying floor painting with ready mix two coats (Excluding priming coat) on new s concrete / masonry / asbestos cement sheet / / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	50.0	13475.00	Rupees Fifty Only
12	438.28	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	72.0	31556.16	Rupees Seventy Two Only
				2959452.04		


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 56
Bangalore - 560 002
02/08